




HIGH SPEED TRAIN – Istanbul/Ankara, TURKEY

Case Study



https://www.tcddtasimacilik.gov.tr/tr/yuksek_hizli_tren



Project Scope

The project encompasses a total of 23 tunnels, each equipped with a lighting control system. Cables have been installed, utilizing a fiber optic internet network infrastructure. Communication, control and monitoring of all tunnels are facilitated through EAE KNX IP Routers connected via this fiber infrastructure. Centralized control is managed by server software located in the Bilecik Station Building within the project.



Fault information generated from the field, along with device connection details and lighting statuses, is transmitted to the Building Management System (BMS), allowing for real-time monitoring and control. To achieve this, one of the Central Monitoring and Control software has been implemented.



In this project, conventional motion sensors have been employed to ensure that the lighting system on the railway tracks activates as trains enter the tunnel and remains illuminated until the trains exit.



Used EAE Technology Devices

| Panel Devices | Quantity |
|---------------------|----------|
| Switch Actuator | 11 |
| IP Router | 146 |
| Dali Gateway | 290 |
| Universal Interface | 156 |









Universal Interface

Switch Actuator

DALI GATEWAY

IP Router